ENGINEERING DEPARTMENT.

KOLAR DISTRICT.

TENDER NOTICE.

Dated 26th February 1927.

Notice is hereby given that sealed tenders will be received by the undersigned at his office at 2 P.M., on 28th March 1927, for the restoration of Bavarahalli-Kallukere Minor Tank Reg. No. 124 of Bowringpet Taluk.

2. No tender will be received after the date and hour above entered.

3. Tenders to be superscribed "Tender for the restoration of Minor Tank."

4. No tender will be received unless accompanied by a deposit of Rs. 100 in cash, currency notes or Treasury receipts.

5. The estimate, plans, etc., will be available at the Executive Engineer's Office between 11 A.M. and 5 P.M.

6. The Executive Engineer, does not bind himself to accept the lowest or any tender or to assign any reason for not accepting any tender.

7. The deposit of the successful tenderer will be retained and will be forfeited by Government if he fails to complete the contract by executing necessary agreement and he will be bound to make good to Government any loss which may arise from such cessation.

8. Restoration work should be started within fifteen days from the date of notification of the acceptance.

9. Any other conditions the contractor may wish to state also be included in his tender.

Statement showing the estimated cost of work for restoring the tank.

Items of work	Per	Quantity	Rate	Cost	Total
BUND.			Rs. a. p.		
Earthwork	C.yds.	3,060			
Turfing	Sqr.	342			
Revetment	C.yds.	68			
Grade stones	Each	19			
Index stones	,,	19			
Registered No. and date stone	,,	1			
Jungle clearing	Each grade	19			
B. M. Stones	Each	2			
Total ...	...	...			
SLUICE.					
Earthwork and refilling the same	C.yds.	45			
Concrete in surki mortar	C.ft.	128			
Burnt brick in surki mortar	,,	375			
Plastering with surki mortar	Sqr.	2·75			
Burnt stone slabs dressed	S.ft.	130			
Cutting holes in orifice slab, etc.	Each	4			
Providing a new plug with lock and key arrangements.	Each	1			
Cast iron pipes (4" dia.)	R.ft.	27			
Dismantling damaged sluice with earthwork, filling, etc., complete.	L. S.	...			
Total ...	...	...			
WEIR.					
Earthwork (gravel with stones)	C.yds.	243			
Concrete in surki mortar	C.ft.	141			
Burnt brick in surki mortar	,,	261			
Burnt stone slabs dressed	S.ft.	115			
Plastering with surki mortar	Sqr.	1			
Rough stone work with new jelly	C.yds.	39			
Cutting joggle joints and fixing stone joggles in surki.	Each	8			
Total ..	...	...			

R. L. STEELE,
Executive Engineer.